

ADDENDUM NO. 1

City of Northlake
Addison Creek Wetland Restoration
Wolf Rd to Palmer Ave

(CBBEL PROJECT NO. 94-32HR243)

Please note the following changes/clarifications to the bid documents:

1. Contractors must purchase bid documents and be shown on the Bidder's Planholder List in order to bid. Bids received by contractors who are not on the Bidder's Planholder List will be rejected. Christopher B. Burke Engineering, Ltd. (CBBEL) will provide a PDF copy of bid documents to bidders on Planholder List if requested.
2. Page 6 Article 108.05. Replace item 2 with the following.
"The second interim completion date is **November 1, 2018**; all remaining work (excluding maintenance and monitoring but including punch list) shall be completed prior to **November 1, 2018**."
Updated page included herein.
3. MWRD UTILIZATION PLAN. The Utilization Plan on UP-1 to UP-7 (page 253 to 260) needs to be completed and submitted with bid. MWRD MBE/WBE/SBE goals must be met for work totaling at least \$1,250,000 of the bid amount.
4. The portion of 8" strip that is not anticipated to be useable as topsoil is anticipated to be sediment. This volume is anticipated to be around 6700 cy, and may need to be hauled from the project site as per the special provision for CHANNEL EXCAVATION (SPECIAL)].
5. The special provision CHANNEL EXCAVATION (SPECIAL) has been revised to include handling/disposal of non-special waste and to include handling/disposal of sediment. Item 66900200 NON-SPECIAL WASTE DISPOSAL has been removed.
Updated pages included herein.
6. The special provision and pay items have been removed. 66900205 SPECIAL WASTE DISPOSAL, 66900450 SPECIAL WASTE PLANS AND REPORTS, 66900530 SOIL DISPOSAL ANALYSIS.
Updated pages included herein.
7. General Note Miscellaneous 4. Replace "Earth Excavation" with "Channel Excavation (Special)".

8. RE: Remove Light Poles and Appurtenances. Contractor shall remove two existing approximately 40 foot light poles and luminaires from peninsula at approximately Station 522+00. Light poles and luminaires shall be delivered to and offloaded at City of Northlake Public Works yard located at 100 W. Palmer Avenue, Northlake, Illinois. Concrete foundations shall be removed and disposed of. The two lights shall be electrically disconnected from adjacent existing lighting control panel located just west of lights. City staff to unlock electrical cabinet for access.
9. RE: Maintenance of Existing Lighting System. For the duration of the project, Contractor shall be responsible for maintenance of existing pathway and park lights within the limits of the construction project in accordance with Special Provision.
10. MWRD MPLA agreement shall be in place for this contract.
11. Valued Engineering proposals will not be reviewed as part of the bid process.
12. Maintenance of Traffic is per Hwy Std as needed for Contractor's means/methods.
13. The special provision and pay item for TEMPORARY INFORMATIONAL SIGNS has been removed.
Updated page included herein.
14. Point Layout Plan (Plan Sheets 28-35) provided for Contractor convenience. All points to be verified by Contractor. All points at limits of disturbance shall meet existing grades.
15. Questions will be accepted until 7:00 am Wednesday 04/05/17. If an addendum is warranted it will be issued by 10:00 am Wednesday 04/05/17.
16. The date and time of the bid opening is still April 7, 2017 at 10:00 am.
17. On-Site Pre-Bid Meeting sign in sheets included herein.

MEETING ATTENDANCE ROSTER

Meeting Details: Thursday, 03/30/17, 9:30 am - 11:30 am. 100 W. Palmer, Northlake, IL 60164

Name	Representing	Phone	Email
1 ERIC TRASKA	CBSEL	(817) 823-0500	ETRASKA@CBSEL.COM
2 BRYAN LUKE	"	"	bluke@cbhel.com
3 Jedd Anderson	"	"	Jedd@cbhel.com
4 DAN DAVINS	E.W.	630 373 6050	DDAVINS@earthworksinchicago.com
5 JOHN CALACCI	DUNN BAR CONSTR.	708 514 5874	J.CALACCI@DUNNBAR.NET
6 TOM TRENKLE	JOHN KEND & CO	647.826.4403	TTRENKLE@JOHNKEND.COM
7 TOM FOSTER	V3	630-724-9200	TFOSTER@V3CO.COM
8 INTIAL AHMED	ACURA INC	630 766 9979 X1004	ESTIMATING@ACURAINC.COM
9 MITCH HOLMER	NATURAL CREATIONS LANDSCAPING INC	815-724-0991	MHOLMER@NATURALCREATIONSLANDSCAPING.COM
10 JOEL D. BERGER	Berger Excavating	847 526 5457	Kberger@bergerexcavating.com
11 Tom Clough	I.H.C.	630/635-0931	TCLOUGH@IHCONSTRUCTION.COM
12 JEFF ELDRIDGE	I.H.C. CONSER	630-903-0258	jeldridge@ihconstructions.com
13 Matt Schultz	Messina Draining	312-718-2166	matt.schultz@globalpump.com
14 Amanda Ramirez	MIDWEST REM	6303067383	amanda@midwestrem.com
15 LEV LADYGA	INDUSTRIA INC	847-331-0126	LEV@INDUSTRIAINC.COM
16			

N:\NORTHLAKE\940032\HR - Municipal Review Projects\940032 HR 2009\940032\HR243\Admin\Agenda_Mtg_AddisonCreekRemainder-940032\HR243_03282017.Docx\NORTHLAKE\940032\HR - Municipal Review Projects\940032 HR 2009\940032\HR243\Admin\Agenda_Mtg_AddisonCreekRemainder-940032\HR243_03282017.docx

1/2

MEETING ATTENDANCE ROSTER

Meeting Details: Thursday, 03/30/17, 9:30 am - 11:30 am. 100 W. Palmer, Northlake, IL 60164

Name	Representing	Phone	Email
1 Joe Krischon	Native Landscapes (contractors)	815-762-6607	joeK@nativeinc.com
2 RICH SIPUK	MARTAM CO.	847-604-6800	RICH@MARTAM.COM
3 Nathan Gorz	Encep	815 757 0472	B.suhayda@cepinc.net
4 Shawn Sinn	Samper F. Land Services	630-518-8484	shawn@samperfi.land
5 ART AImaro	SHERIDAN	630-816-0019	raimara@spands.com
6 Ashley Johnson	Sheridan	847-875-0549	ajohnson@spands.com
7 Mike Healy	RWD DIRTMEN	630-953-1500	mhealy@rwdco.com
8 Mark Wrzeszcz	CBSEL	847 823-0500	mwrzeszcz@cbhel.com
9			
10			
11			
12			
13			
14			
15			
16			

N:\NORTHLAKE\940032\HR - Municipal Review Projects\940032 HR 2009\940032\HR243\Admin\Agenda_Mtg_AddisonCreekRemainder-940032\HR243_03282017.Docx\NORTHLAKE\940032\HR - Municipal Review Projects\940032 HR 2009\940032\HR243\Admin\Agenda_Mtg_AddisonCreekRemainder-940032\HR243_03282017.docx

2/2

ARTICLE 107.09 – PUBLIC CONVENIENCE AND SAFETY

Append the following to this article:

“Contractor shall not work on Saturdays, Sundays, or Holiday Periods without written approval by the ENGINEER.

Contractor shall fence off (snow fence or other; per Article 201.05 (a)) construction site and disturbed areas. This work shall be considered included in the cost of the various removal items.”

ARTICLE 107.23 – PROTECTION OF STREAMS, LAKES, RESERVOIRS, NATURAL AREAS, WETLANDS, PRAIRIE AREAS, SAVANNAHS, AND ENDANGERED AND THREATENED SPECIES.

Prepend the following to this article:

“Per USACE permit requirements, prior to commencement of any in-stream work, Contractor shall submit constructions plans and a detailed narrative that disclose the Contractor’s preferred method of cofferdam and dewatering method to the Engineer. The Engineer will review and forward to North Cook County Soil and Water Conservation District (NC-SWCD).

Work in the waterway shall not commence until the written notification by NC-SWCD that the plans have been approved has been provided to the Contractor.”

ARTICLE 108.05 – COMPLETION DATE WITH INTERIM COMPLETION DATES

Append the following to this article:

“This is a completion date with interim completion dates contract. All work (including maintenance and monitoring) shall be completed by **November 1, 2021**. Engineer will determine substantial completion.

1. The first interim completion date is **January 3, 2018**; all Area A and Area B (including restoration of temporary stock pile and permanent spoil areas) work shall be substantially completed and areas shall be open to the public prior to January 3, 2018.

The area covering the North Soccer area and the South Soccer area shall remain undisturbed and open to the public until July 10, 2017.

The area covering the North Soccer area and the South Soccer area shall remain undisturbed and open to the public after January 3, 2018.

2. The second interim completion date is **November 1, 2018**; all remaining work (excluding maintenance and monitoring but including punch list) shall be completed prior to **November 1, 2018**.”

CHANNEL EXCAVATION (SPECIAL)

Section 203 Append each occurrence of “CHANNEL EXCAVATION” with “ (SPECIAL)”.

Article 203.1 Append the article with the following:

“This work shall also consist of the transportation of suitable excavated materials to embankment locations throughout the limits of the contract, and constructing embankments per Section 205. All embankments shall be keyed into existing slopes and integrally bound to existing materials. The final passes of the finish grader shall be upslope/downslope.

This work shall also consist of excavating the top layer of soils (anticipated depth is shown in the plans) within the disturbance footprint and stockpiling (separate from other spoils, at locations shown in plans) materials classified by the Engineer as acceptable for TOPSOIL PLACEMENT.

This work shall also consist of stockpiling materials at locations shown in plans as needed for Contractor’s means and methods of construction and as needed to complete the grading of the project.

This work shall also consist of disposal of channel excavation (special) determined to be sediment.

This work shall also consist of disposal of channel excavation (special) determined to be non-special waste.

This work also includes all sampling, testing, documentation, dump fees, and associated work required to dispose of the materials off-site in accordance with Section 669.”

TEMPORARY INFORMATIONAL SIGN

Description. ~~This work shall consist of fabricating, installing, maintaining and removing temporary informational signing as detailed in the plans and directed by the Engineer. Signs shall be mounted on Type III barricades.~~

~~Special attention is called to Articles 105.05, and 107.09, and to Sections 701 of the "Standard Specifications", and to Highway Standards, Details, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.~~

~~The Contractor shall contact the Engineer at least 72 hours in advance of installing detour signs. Detour signs shall be installed progressing from the end of the detour route to the beginning.~~

Method of Measurement and Basis of Payment. ~~This work will be measured and paid for at the contract unit prices per square foot for TEMPORARY INFORMATIONAL SIGNS. The payment will be in full for all labor, materials, transportation, and incidentals necessary to furnish, install, maintain, replace, relocate and remove all traffic control devices related to TEMPORARY INFORMATIONAL SIGNS indicated in the plans and special provisions.~~

**CITY OF NORTHLAKE
 CONTRACT DOCUMENTS
 BID PROPOSAL**

I/We hereby agree to furnish to the CITY all necessary materials, equipment, labor, etc. to complete the **Addison Creek Wetland Restoration Wolf Rd to Palmer Ave (CBBEL Project No. 94-32HR243) Project** in accordance with provisions, instructions, and specifications of the CITY for the prices as follows:

BID:

ITEM NO.	ITEMS	UNIT	QUANTITY	UNIT PRICE	TOTAL COST
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	480		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	200		
20100500	TREE REMOVAL, ACRES	ACRE	3.98		
20101000	TEMPORARY FENCE	FOOT	2075		
20101200	TREE ROOT PRUNING	EACH	10		
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	10		
20400800	FURNISHED EXCAVATION	CU YD	50		
20800150	TRENCH BACKFILL	CU YD	30		
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	4961		
25000100	SEEDING, CLASS 1	ACRE	6.08		
25000210	SEEDING, CLASS 2A	ACRE	0.22		
25100115	MULCH, METHOD 2	ACRE	6.3		
25100630	EROSION CONTROL BLANKET	SQ YD	38191		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	200		
25200200	SUPPLEMENTAL WATERING	UNIT	300		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	600		
28000400	PERIMETER EROSION BARRIER	FOOT	4426		
28000500	INLET AND PIPE PROTECTION	EACH	5		

Addison Creek Wetland Restoration
 Wolf Rd to Palmer Ave
 CBBEL Project No. 94-32HR243
 Cook County

ITEM NO.	ITEMS	UNIT	QUANTITY	UNIT PRICE	TOTAL COST
28100105	STONE RIPRAP, CLASS A3	SQ YD	150		
28100107	STONE RIPRAP, CLASS A4	SQ YD	150		
28100109	STONE RIPRAP, CLASS A5	SQ YD	13614		
28100203	STONE RIPRAP, CLASS A2	SQ YD	5845		
28200200	FILTER FABRIC	SQ YD	100		
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	295		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	110		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	500		
42400800	DETECTABLE WARNINGS	SQ FT	24		
44000600	SIDEWALK REMOVAL	SQ FT	250		
54213655	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 10"	EACH	1		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	12		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1		
54214533	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 48"	EACH	1		
550B0330	STORM SEWERS, CLASS B, TYPE 2 10"	FOOT	8		
550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	128		
550B0430	STORM SEWERS, CLASS B, TYPE 2 30"	FOOT	8		
550B0450	STORM SEWERS, CLASS B, TYPE 2 36"	FOOT	16		
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4		
60107600	PIPE UNDERDRAINS 4"	FOOT	3353		
60500040	REMOVING MANHOLES	EACH	1		
60500050	REMOVING CATCH BASINS	EACH	1		
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	XXXXX	XXXXX	XXXXX

Addison Creek Wetland Restoration
 Wolf Rd to Palmer Ave
 CBBEL Project No. 94-32HR243
 Cook County

ITEM NO.	ITEMS	UNIT	QUANTITY	UNIT PRICE	TOTAL COST
66900205	SPECIAL WASTE DISPOSAL	CU YD	XXXXX	XXXXX	XXXXX
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	XXXXX	XXXXX	XXXXX
66900530	SOIL DISPOSAL ANALYSIS	EACH	XXXXX	XXXXX	XXXXX
67100100	MOBILIZATION	L SUM	1	\$50,000.00	\$50,000.00
C2000436	SHRUB, ARONIA ARBUTIFOLIA BRILLIANT ISSIMA (BRILLIANT RED CHOKEBERRY), 3' HEIGHT, BALLED AND BURLAPPED	EACH	29		
X0324082	RIFLE STRUCTURE	EACH	6		
X0327036	BIKE PATH REMOVAL	SQ YD	613		
X0426200	DEWATERING	L SUM	1		
X2030300	CHANNEL EXCAVATION (SPECIAL)	CU YD	48768		
X2111110	TOPSOIL PLACEMENT	CU YD	6729		
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	20		
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		
XX000503	SPLIT RAIL FENCE	FOOT	272		
XX008645	TEMPORARY INFORMATIONAL SIGNS	EACH	XXXXX	XXXXX	XXXXX
XXX00001	TREE, ACER X FREEMANII ARMSTRONG (ARMSTRONG FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	16		
XXX00002	TREE, ACER MIYABEI MORTON (STATE STREET MIYABE MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	15		
XXX00003	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	22		
XXX00004	TREE, GLEDITSIA TRIACANTHOS INERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	11		
XXX00005	TREE, JUGLANS NIGRA (BLACK WALNUT), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	12		
XXX00006	TREE, PLATANUS OCCIDENTALIS (SYCAMORE), 2-1/2" CALIPER, BALLED	EACH	6		

Addison Creek Wetland Restoration
 Wolf Rd to Palmer Ave
 CBBEL Project No. 94-32HR243
 Cook County

ITEM NO.	ITEMS	UNIT	QUANTITY	UNIT PRICE	TOTAL COST
	AND BURLAPPED				
XXX00007	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6		
XXX00008	TREE, SALIX NIGRA (BLACK WILLOW), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6		
XXX00009	TREE, CARYA CORDIFORMIS (BITTERNUT HICKORY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6		
XXX00010	TREE, CARYA OVATA (SHAGBARK HICKORY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6		
XXX00011	TREE, QUERCUS MACROCARPA (BUR OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6		
XXX00012	TREE, QUERCUS ALBA (WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6		
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	700		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		
ZZCBBEL01	SEEDING (SPECIAL) - NATIVE PRAIRIE GRASSLAND	ACRE	3.6		
ZZCBBEL02	SEEDING (SPECIAL) - WET-MESIC PRAIRIE GRASS MIX	ACRE	4.29		
ZZCBBEL03	INTERSEEDING (SPECIAL) - NATIVE PRAIRIE GRASSLAND	ACRE	3.6		
ZZCBBEL04	INTERSEEDING (SPECIAL) - WET-MESIC PRAIRIE GRASS MIX	ACRE	4.29		
ZZCBBEL05	DAM REMOVAL (LOCATION NO 1)	EACH	1		
ZZCBBEL06	DAM REMOVAL (LOCATION NO 2)	EACH	1		
ZZCBBEL07	COFFERDAMS (SPECIAL)	L SUM	1		
ZZCBBEL08	BYPASS PUMPING	L SUM	1		
ZZCBBEL09	GABIONS	CU YD	295		
ZZCBBEL10	MAINTENANCE AND MONITORING	YEAR	4		
ZZCBBEL11	MAINTENANCE OF EXISTING LIGHTING SYSTEM	L SUM	1		
ZZCBBEL12	REMOVE LIGHT POLES AND APPURTENANCES	EACH	6		
ZZCBBEL13	SAND TOPPING, 2"	SQ YD	23450		

ITEM NO.	ITEMS	UNIT	QUANTITY	UNIT PRICE	TOTAL COST
ZZCBBEL14	ITEMS AS DIRECTED BY THE ENGINEER	EACH	90000	\$1.00	\$90,000.00
BIDDER'S PROPOSAL FOR MAKING ENTIRE IMPROVEMENT (BID)					

(FIGURES)

BIDDERS PROPOSAL FOR MAKING ENTIRE IMPROVEMENT (BID)

(WORDS)

Please acknowledge the receipt of this addendum by signing the acknowledgement and emailing a copy to bluke@cbbel.com, with vcaro@cbbel.com Cc'd on that email.

This addendum needs to be signed and included with the sealed bid.

Failure to properly acknowledge this addendum as noted above may result in disqualification of the associated bid.

END OF ADDENDUM NO. 1

I acknowledge the receipt of Addendum #1 for the above referenced project:

Signed:

Name

Name of Company

ADDENDUM NO. 2

City of Northlake
Addison Creek Wetland Restoration
Wolf Rd to Palmer Ave

(CBBEL PROJECT NO. 94-32HR243)

Please note the following changes/clarifications to the bid documents:

1. Construction queueing may be on City streets during working hours, with appropriate traffic control and protections measures provided by Contractor. At least one lane of travel and all turn lanes shall remain open at all times.
2. Substantial completion will be at the end of the 2nd interim completion date.
3. Substantial Completion Performance bond has been revised to 100% of the amount of the bid and shall be in effect from Notice to Proceed through Substantial Completion.
Updated page included herein.
4. Maintenance and Monitoring Performance Bond shall be in effect from Substantial Completion through the end of the Maintenance and Monitoring Period.
Updated page included herein.
5. MWRD UTILIZATION PLAN. MWRD MBE/WBE/SBE percentage goals must be met for work totaling at least \$1,250,000 of the bid amount. MBE = 20% of \$1,250,000, WBE = 10% of \$1,250,000, SBE = 10% of \$1,250,000.
6. Note that Areas A, B and C refer to the creek. Stockpile areas and soccer fields are independent.
7. Gabions. Backfill material "Porous Granular Embankment, Special" shall be CA 8 thru CA18, FA 1 thru FA 4, FA 7 thru FA 9 and FA 20, according to Articles 1003 and 1004.
8. Stone riprap can be quarried, except for Riffles as noted in plan details.
9. Owner shall verify classification of excavated materials as sediment. Sediment shall be considered as Channel Excavation (Special). Excavated materials not used per plan shall be hauled off site per the Special Provisions.
10. Special Waste shall be handled per Article 107.19.
11. Compensation will be provided as noted in the Special Provisions.

12. Cofferdams schematics show 5' diameter bypass flow. Information on flow rates provided in plans. Contractor is responsible for design that meet's Contractor's means/methods and permit requirements. All water control elements shall be able to be manually opened. Contractor shall manage water levels and control sediment and erosion.

13. The date and time of the bid opening is still April 7, 2017 at 10:00 am.

CITY OF NORTHLAKE
CONTRACT DOCUMENTS
FOR

**Addison Creek Wetland Restoration
Wolf Rd to Palmer Ave**

(CBBEL PROJECT NO. 94-32HR243)

Pre-Bid On-Site Meeting Date and Time Thursday, March 30, 2017 10:30 a.m.
Bid Opening Date: Friday, April 7, 2017
Bid Due By: 10:00 a.m.
Bid Opening Time: 10:00 a.m.
Bid Opening Location: City Hall
Bid Deposit: 10% of the Amount of Bid
Substantial Completion Performance Bond: 100% of the Amount of Bid
Maintenance and Monitoring Performance Bond: 10% of the Amount of Bid

Obtain Information From:

Mark Wrzeszcz
Christopher B. Burke Engineering, Ltd.
9575 West Higgins Road, Suite 600
Rosemont, IL 60018
(847) 823-0500

Submit bids to:

Nancy Pauletto, City Clerk
City Hall
City of Northlake
55 East North Avenue
Northlake, IL 60164
(708) 343-8700

Note: This cover sheet is an integral part of the contract documents and is, as are all of the following documents, part of any contract executed between the City of Northlake and any successful BIDDER. Do not detach any portion of this document. Invalidation could result.

ARTICLE 108.09 – FAILURE TO COMPETE THE WORK ON TIME

Append each occurrence of “completion date” with: “and interim completion dates”

PERFORMANCE BOND

Substantial Completion Performance Bond shall be held by the Owner until all work associated with the first interim completion date and the second interim completion date is completed to the satisfaction of the Owner. The work shall include all establishment periods. The Performance Bond Shall be for 100% of the amount of bid.

Maintenance and Monitoring Performance Bond shall be held by the Owner. This Bond shall be in the amount of 10% of the amount of bid, and shall be in force from Substantial Completion to Final Completion, which included the Maintenance and Monitoring period.

PREVAILING WAGE RATES

When engaged in construction of a “public work,” within the meaning of Illinois Prevailing Wage Act, 820 ILCS 130/.01 et seq. (“the Act”), the Act requires Contractors and Subcontractors to pay laborers, workers and mechanics performing services on public works projects no less than the “prevailing rate of wages” (hourly wages plus fringe benefits) in the county where the work is performed.

For information regarding current prevailing wage rates, please refer to the Illinois Department of Labor’s website at: www.state.il.us/agency/idol/rates/rates.HTM. All Contractors and Subcontractors rendering services under a Contract for the construction of a public work must comply with all requirements of the Act, including but not limited to, all wage, notice and record keeping duties.

The term general prevailing hourly rate, when used in this requirement will mean the hourly cash wages plus fringe benefits for health and welfare, insurance, vacations and pensions paid generally, in the locality in which the work is being performed, to employees engaged in work of a similar character on public works.

As a condition of making payment to the Contractor, the City may require the Contractor to submit an affidavit to the effect that not less than the prevailing hourly wage rate is being paid to laborers, mechanics and other workmen employed on this Contract in accordance with Illinois or federal law, as applicable.

SECTION 671 MOBILIZATION

Revise the first paragraph of Article 671.02 to the following:

Replace the second sentence with “The Contractor will receive payment in the amount of \$50,000.00, according to the following schedule.”

Please acknowledge the receipt of this addendum by signing the acknowledgement and emailing a copy to bluke@cbbel.com, with vcaro@cbbel.com Cc'd on that email.

This addendum needs to be signed and included with the sealed bid.

Failure to properly acknowledge this addendum as noted above may result in disqualification of the associated bid.

END OF ADDENDUM NO. 2

I acknowledge the receipt of Addendum #2 for the above referenced project:

Signed:

Name

Name of Company