

ADDENDUM NO. 1

December 4, 2017

To:

Contract Documents Entitled
Sunnyside Sanitary Sewer Replacement Project
IEPA Loan Project No. L174937

Bid Due Date: December 12, 2017, 10:00 a.m.

For:

Village of Westchester

Prepared By:

Christopher B. Burke Engineering, Ltd.

[CBBEL Project No.: 110598.00001]

This Addendum forms part of the Contract Documents and modifies the original Bidding Documents as noted below. Acknowledge receipt of this Addendum by returning the attached acknowledgement of receipt of Addendum form by fax to 847-823-0520 and including copy with submitted bid proposal. Failure to do so may subject Bidder to disqualification.

This Addendum consists of the following changes and clarifications:

1. **Sanitary Sewer Pipe Material:** The sanitary sewer pipe to be installed for the Project is changed from "PVC SDR 26 (PR160) in accordance with ASTM D2241" to "PVC AWWA C900/905 DR 25". The joint specification remains the same and shall conform to ASTM D3139 with gaskets meeting the requirements of F477.
 - a. The pipe material change includes Specification Section 33 31 14 [Sewers, Manholes and Accessories]: par. 202B., "PVC Pipe", and; par. 4.02A, "Payment".
2. **Bid Schedule:** The Bid Schedule has been revised to reflect the pipe material change (Item #1), and is attached for use in submitting bids for this Project.
3. **IDOT Permit Application:** IDOT has not finished the Permit application review and approval at this time. However, IDOT has informed us that the Highway Permit Bond amount will be \$30,000. All costs to furnish and secure this IDOT Highway Permit Bond shall be included in the total cost of the Contract.
4. **Maintenance of Traffic (MOT):** A MOT Plan for Project construction is required to be submitted to the Village for review and approval prior to starting the work.
 - a. Since the IDOT Permit Application approval has not been received to date, the MOT requirements are not known for work on and along 31st Street (state highway). Therefore, contractors should assume that lane closures on 31st Street will not be allowed when preparing their respective bids for this Project.
 - b. The contractor will be permitted to fully close Sunnyside Avenue while

construction work occurs in this area. Access will still need to be provided for local traffic.

5. The contractor will be required to coordinate their work with the MWRD in order to gain access to the MWRD manhole (Brainard and Jackson) to perform the CIPP lining of the 30" sewer pipe connecting to the MWRD Interceptor.
6. The silt fence as shown on the Drawings along Sunnyside Avenue can be moved by the contractor at his own discretion. However, tree removal on FPDCC property is not allowed for this contract and the contractor shall assume all responsibility for the contractor's activities on FPDCC property.
7. Additional soil borings can be performed along the proposed sewer alignment at the contractor's own time and expense. However, the contractor must seek permission from the jurisdiction in charge at the proposed soil boring locations. The following contacts are provided for the contractor's convenience:
 - a. Village of Westchester: Robert Lewis (708-345-0041).
 - b. Village of LaGrange Park: Brendan McLaughlin (708-352-2922)
 - c. FPDCC: John Sterenberg (708-771-1192)
8. **Edgewood Ave. Access:** Edgewood Ave. is part of the FPDCC bike/hiking trail. The contractor is required to allow an approximate 6-foot wide fenced off (snow/construction fence) access way at all times for biking and hiking activities.
9. **Construction Schedule:** The Project is being funded via an IEPA low interest loan. Final approvals of the IEPA and the contract award is anticipated in the mid-February/early March time frame at which time the Notice to Proceed will be provided to the contractor to start construction.
10. Blasting for rock excavation will not be permitted.
11. Any PCC sidewalk, curb and gutter and/or pavement that is not specifically shown and/or specified to be removed and replaced and that is damage by the contractor shall be repaired and/or removed and replaced at the contractor's expense.
12. The steel casing pipe that is proposed for installation beneath 31st Street (Bid Item No. 33 31 14/05) and Salt Creek (Bid Item No. 33 31 15/01) is changed from a 42" diameter to a 48" diameter. This change is reflected in the attached Revised Bid Schedule.

Attachments: Revised Bid Schedule (pages 15 and 16).

END OF ADDENDUM NO. 1

Village of Westchester

Sunnyside Sanitary Sewer Replacement Project

IEPA Loan Project L174937

[CBBEL Project No. 01.R110598.00001]

ADDENDUM #1

I acknowledge the receipt of Addendum #1 for the above referenced project:

Signed:

Name

Name of Company

Date

DS/pjb

N:/Westchester/110598/Admin/Project Bidding/Sunnyside Addendum 1 (120417).docx

Bidder agrees to perform all the work described in the Contract Documents for the following unit prices or lump sum:

BID SCHEDULE

NOTE: Bids shall include all Bonds and Insurance, sales tax and all other applicable taxes and fees.

ITEM NO.	ITEMS	QUANTITY	UNIT	UNIT PRICE	TOTAL
01 13 00/01	MOBILIZATION & DEMOBILIZATION	1	LS		
01 50 00/01	MAINTENANCE & CONTROL OF TRAFFIC	1	LS		
01 50 00/02	FPDCC STAGING AREA	1	LS		
01 71 15/01	CONSTRUCTION LAYOUT	1	LS		
31 10 12/01	TREE REMOVAL & PROTECTION	1	LS		
31 10 14/01	PERIMETER EROSION BARRIER	17,000	LF		
31 10 14/02	INLET PROTECTION FILTERS	7	EA		
31 23 16/01	ROCK EXCAVATION	3,700	CY		
31 23 18/01	TRENCH BACKFILL (CA-6)	2,185	LF		
32 12 16/01	BITUMINOUS PAVEMENT REPLACEMENT	2,800	SY		
32 12 16/02	BITUMINOUS BIKE PATH REPLACEMENT	1,140	SY		
32 12 16/03	COMBINATION CONCRETE CURB & GUTTER REMOVAL & REPLACEMENT	52	LF		
32 12 18/01	PCC DRIVEWAY REMOVE AND REPLACE	30	SY		
32 12 18/02	REMOVE & REPLACE 8" CMP WITH FES	20	LF		
32 12 18/03	REMOVE & REPLACE 12" CMP WITH FES	32	LF		
32 16 23/01	PCC SIDEWALK REMOVAL & REPLACEMENT	80	SF		
32 16 23/02	SIDEWALK REMOVAL	772	LF		
32 92 19/01	TOP SOIL / SEED AND BLANKET	3,200	LF		
33 31 14/01	8" PVC C900 SEWER IN OPEN CUT TRENCH	34	LF		
33 31 14/02	10" PVC C900 SEWER IN OPEN CUT TRENCH	350	LF		
33 31 14/03	24" PVC C900 SEWER IN OPEN CUT TRENCH	618	LF		
33 31 14/04	30" PVC C900 SEWER IN OPEN CUT TRENCH	4,020	LF		
33 31 14/05	48" STEEL CASING, AUGERED IN ROCK WITH 30" PVC C900 CARRIER PIPE	92	LF		

ITEM NO.	ITEMS	QUANTITY	UNIT	UNIT PRICE	TOTAL
33 31 14/06	STANDARD MANHOLES, 5' DIA., 10' DEEP AND UNDER, INSTALLED COMPLETE	21	EA		
33 31 14/07	DOG HOUSE MANHOLES, 5' DIA., 10' DEEP AND UNDER, INSTALLED COMPLETE	4	EA		
33 31 14/08	RISER SECTIONS FOR 5' DIA. MANHOLES FOR DEPTHS OVER 10'	170	VF		
33 31 14/09	STANDARD DROP CONNECTIONS	2	EA		
33 31 14/10	CONNECTION/RECONNECTION TO NEW MH	1	EA		
33 31 14/11	MANHOLE ABANDONMENT (ACCESSIBLE)	10	EA		
33 31 14/12	MANHOLE ABANDONMENT (LID WELDED TO FRAME)	23	EA		
33 31 15/01	SALT CREEK CROSSING	1	LS		
33 31 22/01	CIPP LINING FOR 30" SEWER	220	LF		
TOTAL OF BID (Including Bonds & Insurance)					\$

Bidder is currently certified as an MBE or WBE under EPA's DBE Program? Yes ___ No ___

Respectfully submitted:

_____	_____
Signature	Address
_____	_____
Title	Date
_____	_____
Telephone #	E-mail Address

(SEAL - if BID is by a corporation)

Attest _____